ECMLK3125



3 Phase Main Lug Kit 100A - 125A

Hazardous Voltage.

Will cause death, serious injury

or substantial property damage.

equipment before working inside.

Turn off power supplying this



## MAIN LUG KIT INSTALLATION INSTRUCTIONS



## DANGER

## **A** SAFETY INSTRUCTIONS

**Note:** This instruction outlines the recommended installation procedure. For installation by a qualified person, as defined by all local electrical codes and/or the National Electrical Code®.

- 1. Turn off and lock out the power supplying the load center before working inside.
- 2. Remove 1/4-20 nuts from bus studs and remove main lugs.
- 3. Install lugs on bus studs as shown, fasten with 1/4-20 nuts (provided). Tighten to 40-45 lb-ins.

481000260101 Rev.A

Siemens Industry, Inc. Norcross, Georgia U.S.A.

"-- D--t--ti-- A----i-ti--

