


CATALOG NUMBER

**ECMLK3225**

**electricCenter**  
ACCESSORIES

**3 Phase Main Lug Kit  
150A - 225A**



0 40892 65190 4

## MAIN LUG KIT INSTALLATION INSTRUCTIONS



### **⚠ DANGER**

**Hazardous Voltage.**  
Will cause death, serious injury  
or substantial property damage.

Turn off power supplying this  
equipment before working inside.

### **⚠ SAFETY INSTRUCTIONS**

**Note:** This instruction outlines the  
recommended installation procedure.  
For installation by a qualified person,  
as defined by all local electrical codes  
and/or the National Electrical Code®.

1. Turn off and lock out the power supplying the load center before working inside.
2. Remove 1/4-20 nuts from bus studs and remove main breaker or main lugs.
3. Install lugs on bus studs as shown, fasten with 1/4-20 nuts (provided). Tighten to 40-45 lb-ins.
4. If necessary, obtain and install Main Breaker Filler Plate EC3PMFP1.

Siemens Industry, Inc. Norcross, Georgia U.S.A.

481000270101 Rev.A

® The National Electrical Code is a registered trademark of the National Fire Protection Association.

© 2011 Copyright Siemens Industry, Inc.

Assembled in Mexico

